

Fiscal Services
1800 Ignacio Blvd
Novato CA 94949
415-884-3162

**PROJECT: KENTFIELD – FUSSELMAN HALL BOILER DESIGN-BUILD BOILER
PLANT, CONTROLS SYSTEM & HAZARDOUS MATERIALS ABATEMENT
PROJECT #16-0408**

ADDENDUM #3

April 29, 2016

Marin Community College District

ADDITIONAL INFORMATION

NONE

REVISIONS/CLARIFICATIONS

BQ#5 Who is responsible for the monitoring of the asbestos abatement and who will be running the air clearance samples?

Answer: The District will provide air clearance sampling and abatement monitoring by American Compliance, Inc.

BQ#6 Will there be areas that are impacted by lead paint drilling or cutting during the project? If so, are we to just remove around the areas of paint at points of impact?

Answer: Depending on awarded Alternates the Abatement Contractor should expect any work installed in Mechanical Room 25 will likely involve penetrations in existing drywall ceilings with ACM Tape Compound and concrete walls that contain Lead Paint. Removal of ACM and Lead Paint is limited to affected areas only and must remain in compliance with OSHA 1529.